D2: Was the plan revised to reflect progress in local mitigation efforts? See status column.

D3: Was the plan revised to reflect changes in priorities? See discussion on how they were prioritized, page 5-27.

Note: References to culverts on the following pages refer to upsizing or lengthening culverts, unless otherwise stated. Over the years, FEMA has established project useful life standards for typical mitigation project types. FEMA's project useful life standard for culverts ranges from 25-50 years, depending on type of materials used. Other examples are: generators - 19 years, elevations – 30 years, and acquisition/demolitions - 100+ years.

Aroostook County Projects

| Town | | Estimated | Time | Responsible | |
|---------------------------------|---|-----------|-----------------|--------------|--------------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| Allagash | 1) Frank Mack Road - Upsize 24' cmp to | | | Road | Deferred – Lack of |
| | 48" x 40', rip rap | \$13,500 | Medium Term | Commissioner | funds |
| | 2) Walter Brook Road - Install (2)24" x 40' | | | Road | Deferred – Lack of |
| | cmps & (2) 36" x 40'cmp's, rip rap | \$9,000 | Medium Term | Commissioner | funds |
| | 3) Inn Road - Bank stabilization, culvert | | | Road | Deferred – Lack of |
| | | \$5,000 | Short Term | Commissioner | funds |
| | 4) Old Rapid Road - Culvert | _ | | Road | Deferred – Lack of |
| | | \$60,000 | Medium Term | Commissioner | funds |
| Aroostook Band of Micmacs | Please see Annex for updates on Tribe project | ets | | | |
| Ashland | 1) Wrightville Road - Ditching & culverts | | | | Deferred – Lack of |
| | | \$120,000 | Long Term | Public Works | funds |
| Blaine | 1) Grass Road - Place geo fabric and | | | | Deferred – Lack of |
| | elevate 125' section of road 7 repave | \$8,000 | Long Term | Public Works | funds |
| | 2) Robinson Road - Upsize 48' x 70' culvert | _ | | | Deferred – Lack of |
| | | \$10,500 | Medium Term | Public Works | funds |
| | 3) Barrett Road - Upsize 48' x 40' cmp | \$6,500 | Medium Term | Public Works | Deferred – Lack of funds |
| | 4) Pierce Road - One culvert | ψ0,500 | Mediaiii Teiiii | Fublic Works | Deferred – Lack of |
| | 4) Fleice Road - One culvert | \$3,000 | Medium Term | Public Works | funds |
| | 5) Libby Road - One culvert. | \$6,000 | Medium Term | Public Works | Deferred – Lack of funds |

| Town | | Estimated | Time | Responsible | |
|----------------|--|-----------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 1) East Blaine Road – Upsize culvert (size | | | Road | Deferred – Lack of |
| Bridgewater | to be determined)/bridge | \$95,000 | Medium Term | Commissioner | funds |
| | 2) Packard Road – Ditch 15,000', add (6) | | | Road | Deferred – Lack of |
| | 18"' x 40' cmps | \$33,000 | Medium Term | Commissioner | funds |
| | 3) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Caribou | 1) Madawaska Road – Upsize culvert | \$10,000 | Completed | Public Works | Completed |
| | 2) Plant Road – Upsize culvert | \$15,000 | Completed | Public Works | Completed |
| | 3) Ogren Road – Upsize culvert | \$9,000 | Completed | Public Works | Completed |
| | 4) River Road – Easements, engineering | | | | Deferred – Lack of |
| | and soil evaluations | \$156,000 | Long Term | Public Works | funds |
| | 5) Install dry hydrants | | | | Deferred – Lack of |
| | | \$1,000 | Short Term | Public Works | funds |
| | 6) Farnham Brook – upsize culvert and rip | | | | |
| | rap | \$150,000 | Completed | Public Works | Completed |
| | 7) Limestone Street – stabilize bank that is | | | | Deferred – Lack of |
| | eroding into river | TBD | Short Term | Public Works | funds |
| | 8) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Castle Hill | 1) McDonald Road – Install 5' x 50' cmp | \$6,800 | Completed | Public Works | Completed |
| | 2) Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| Caswell | Willard Road – Ditch 6.5 miles, upsize (2) | | | | Deferred – Lack of |
| | 24" cmps to 48" x 40' cmps | \$73,000 | Long Term | Public Works | funds |
| Chapman | Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| Cyr Plantation | 1) Laplante Road – Rebuild 300 feet | | | Road | Deferred – Lack of |
| | | \$14,000 | Long Term | Commissioner | funds |
| | 2) Madore Road – Rebuild 800 feet | \$37,500 | | Road | Deferred – Lack of |
| | | | Long Term | Commissioner | funds |
| | 3) Michelle L. Cross Road – Rebuild 2,000 | | | Road | Deferred – Lack of |
| | feet | \$95,000 | Long Term | Commissioner | funds |

| Town | | Estimated | Time | Responsible | |
|------------------|--|-------------|-------------|---------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 4) Omer Dumond Road – Install one | | | Road | Deferred – Lack of |
| (Cyr Plantation) | corrugated metal pipe | \$5,000 | Short Term | Commissioner | funds |
| | 5) LaPlante Road – Rebuild 800 feet | | | Road | Deferred – Lack of |
| | | \$37,500 | Long Term | Commissioner | funds |
| Dyer Brook | 1) Pond Road – Upgrade with new culverts | unknown | Short Term | Public Works | Completed 2020 |
| | and paving | | | | |
| | 2) Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| Eagle Lake | Gillmore Brook Road – Ditch 20,000', add | | | | Deferred – Lack of |
| | surface gravel 5.5 miles x 20' x 6' | \$129,000 | Long Term | Public Works | funds |
| Easton | 1) Hersom Road – Mitigate drainage issues | \$65,000 | Medium Term | Public Works | New Project |
| | 2) Graham Road – Upsize twin 3' cmps | | | | |
| | with 8' x 40' box culvert, rip rap & upsize | \$68,000 | Medium Term | Public Works | Completed |
| | guard rails | | | | |
| | 3) Ladner Road – Upsize twin 3' cmps with | | | | |
| | 8' x 45' culvert, rip rap & upsize guard rails | \$73,000 | Medium Term | Public Works | Completed |
| Fort Fairfield | 1) Currier Road – Install 12' x 60' box | | | Road | Deferred – Lack of |
| | culvert, rip rap,raise road & repave | \$149,000 | Long Term | Commissioner/ | funds |
| | | | | Selectmen | |
| Fort Kent | 1) Shore Guard Levee Protection – Fish | | | | Deferred – Lack of |
| | River | \$500,000 | Long Term | Public Works | funds |
| | 2) Bradbury Road – Study option of re- | | | | Deferred – Lack of |
| | routing to 11 South – avoid major landslide | \$1,000,000 | Long Term | Public Works | funds |
| | and residents being stranded | | | | |
| | Bradbury Road – Document progression | | | | Upsized by # 2, |
| | for future mitigation | \$15,000 | Long Term | Public Works | above |
| | Bradbury Road – Culverts to allow run off | | | | Upsized by # 2, |
| | to flow | \$10,000 | Long Term | Public Works | above |
| | 3) Charette Hill Road – Bank stabilization, | | | | Deferred – Lack of |
| | erosion control | \$120,000 | Long Term | Public Works | funds New Project |
| | 4) Heritage Trail – Culvert and bank | ' | | | Deferred – Lack of |
| | stabilization | \$5,000 | Short Term | Public Works | funds |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|---------------|--|-----------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 5) North Perley Brook Road – Upsize | | | | Competed; HMPG |
| (Fort Kent) | culverts to reduce flooding | \$18,837 | Short Term | Public Works | grant, August 2015 |
| | 6) East Main Street – Acquire homes, | | Partially | | Some homes |
| | demolish & expand park | \$250,000 | Completed | Public Works | acquired |
| | 7) South Pearly Brook Road – Upsize | | | | |
| | culvert with larger one | \$10,000 | Completed | Public Works | Completed |
| | 8) Public Works Department – Relocate | | | | |
| | garage out of flood zone | \$20,000 | Completed | Public Works | Completed |
| | 9) Violette Settlement Road – Upsize | | | | |
| | culvert with larger one and raise the road | \$20,000 | Completed | Public Works | Completed |
| | 10) Aroostook School Road - Improve | | | | |
| | drainage | \$10,000 | Completed | Public Works | Completed |
| | 11) Marquis Road – upsize culvert with | | | | |
| | larger one | \$10,000 | Completed | Public Works | Completed |
| | 12) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| | 13) Little Black Lake – culvert upgrade, | | | | Deferred – Lack of |
| | riprap | \$20,000 | Short Term | Public Works | funds |
| | 1) Gagnon Road – Study drainage | | | | |
| Frenchville | improvements at Bridge 2391 | \$110,000 | Short Term | Public Works | Completed in 2015 |
| | 2) Starbarn Avenue - Work on ditches to | | | | |
| | prevent erosion | \$7,822 | Medium Term | Public Works | Completed in 2013 |
| | 3) Pelletier Ave. – Study drainage | | | | |
| | improvements | \$14,062 | Long Term | Public Works | Completed in 2013 |
| | 4) Church Avenue - Ditching and erosion | | | | |
| | control | \$9,541 | Medium Term | Public Works | Completed in 2015 |
| | 5) Pelletier Avenue - Upgrade culvert and | | | | - |
| | road | \$9,059 | Long Term | Public Works | Completed in 2014 |
| | 6) Starbarn Avenue - Upgrade road and | | | | • |
| | ditching | \$26,362 | Long Term | Public Works | Completed in 2015 |
| | 7)Starbarn Avenue - Ditch and divert water | | Ĭ | | • |
| | | \$5,322 | Short Term | Public Works | Completed in 2013 |

| Town | | Estimated | Time | Responsible | |
|---------------|---|-----------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 8) Bourgoin Avenue - Ditch and culvert | | | | |
| (Frenchville) | upsize | \$5,567 | Short Term | Public Works | Completed in 2012 |
| | 9) Pelletier Avenue - Erosion control | | | | Deferred – Lack of |
| | | \$5,267 | Medium Term | Public Works | funds |
| | 10) Pelletier Avenue - Remove trees, | | | | |
| | realign road | \$3,067 | Medium Term | Public Works | Completed in 2011 |
| | 11) Pelletier Avenue - Upsize culvert, | | | | Deferred – Lack of |
| | drainage | \$1,362 | Short Term | Public Works | funds |
| Garfield Plt. | 1) Upgrade roads & bridges as necessary | | | | Deferred – Lack of |
| | to reduce flood hazard | \$25,000 | Long Term | Public Works | funds |
| | 2) Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| Grand Isle | 1) Grivois Road - Ditch 25,000' of road and | | | | Deferred – Lack of |
| | install (8) 18" x 24' cmps | \$75,000 | Long Term | Public Works | funds |
| | 2) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Hamlin | Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| Haynesville | Skagrock Road - Ditch 10,000' upsize | | | | Deferred – Lack of |
| | culvert to 5' x 30' box culvert, rip rap | \$58,000 | Medium Term | Public Works | funds |
| Hodgdon | 1) McIntyre Road - 800 feet road elevation | | | | Deferred – Lack of |
| | | \$37,500 | Long Term | Public Works | funds |
| | 2) Westford Hill Road - 600 feet road | | | | Deferred – Lack of |
| | elevation | \$27,500 | Long Term | Public Works | funds |
| | 3) North Town Line Road - 1,000 feet road | | | | Deferred – Lack of |
| | elevation | \$47,500 | Long Term | Public Works | funds |
| | 4) Green Road - 2,000 feet road elevation | | | | Deferred – Lack of |
| | | \$95,000 | Long Term | Public Works | funds |
| | 5) South McIntyre Road - One culvert | | | | Deferred – Lack of |
| | | \$3,000 | Short Term | Public Works | funds |
| | | | | | |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|------------------------|--|-----------|-------------|--------------|--|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| Houlton | 1) Morningstar Road - At Moose Brook determine proper size and upsize 12' x 60' culvert | \$100,000 | Medium Term | Public Works | Under contract – to be completed Fall 2021 |
| | 2) Runway drainage at Houlton International Airport - Install debris catcher at inflow of pipe | \$30,000 | Completed | Public Works | Completed |
| | 3) Green Street - Acquisition & demolish house at 12 Greet Street., project returned to open space | \$83,000 | Completed | Public Works | Completed |
| | 4) Lincoln Street - Acquire & demolish house at 3 Lincoln Street, returned to open space | \$65,000 | Completed | Public Works | Completed |
| | 5) Cutting back branches from lines to resolve power issues | \$45,000 | Completed | Public Works | Completed |
| Houlton Band | 1) Bell Road – Resize and replace water crossing. | \$200,000 | Long Term | Public Works | New |
| of Maliseet Indians | 2) Wilderness Pines – Establish internet service for non-congregate sheltering | \$40,000 | Medium Term | Public Works | New |
| | 3 Bell Road – Extend road to Carson Road for egress from Administration building | \$200,000 | Medium Term | Public Works | New |
| Island Falls | 1) Old Patten Road - Install 122" x 50' floodway arch culvert, rip rap & repave | \$22,000 | Medium Term | Public Works | Deferred – Lack of funds |
| | 2) Jacob Shur Road - Upsize culverts – build up road | \$15,000 | Long Term | Public Works | Deferred – Lack of funds |
| | 3) Merriman Road - Culverts and ditching | \$25,000 | Long Term | Public Works | Deferred – Lack of funds |
| | 4) South Shore Road - Ditching | \$15,000 | Short Term | Public Works | Deferred – Lack of funds |
| | (5) Sewall Street - Drainage, ditching | \$20,000 | Short Term | Public Works | Deferred – Lack of funds |
| | 6) Church Street - Drainage, ditching | \$20,000 | Short Term | Public Works | Deferred – Lack of funds |

| Town | | Estimated | Time | Responsible | |
|----------------|---|------------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 7) Acquisition/demolition – 1 property; | | | Contractor | Completed 2012 |
| (Island Falls) | deed restricted to open space | \$18,470 | Completed | Public Works | PDM grant |
| Limestone | 1) Burleigh Street - Underground storm | | | | |
| | drain; install (2) catch basins and 450' x 4' | \$64,000 | Long Term | Public Works | Deferred – Lack of |
| | culvert | | | | funds |
| | 2) Silver Spring Brook - Dredge brook at | | | | Deferred – Lack of |
| | intake | \$20,000 | Long Term | Public Works | funds |
| | (3) Cutting back branches | | | | Deferred – Lack of |
| | | \$45,000 | Short Term | Public Works | funds |
| | 4) Stabilize bank to protect sewer | | | | Deferred – Lack of |
| | | \$87,000 | Medium Term | Public Works | funds |
| | 5) Madawaska Dam - Resurface spillway | | | | Deferred – Lack of |
| | with proper material | \$100,000 | Long Term | Public Works | funds |
| | 6) Fish Way to Madawaska Dam | | | | Deferred – Lack of |
| | | \$250,000 | Long Term | Public Works | funds |
| | 7) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Linneus | 1) South Oakfield Road-Beaver Brook - | | | | |
| | Upsize & enlarge existing culvert, from 5' to | \$18,000 | Short Term | Road | Deferred – Lack of |
| | 6'. Install 2' overflow. Rip rap. Resurface | | | Commissioner | funds |
| | 300; of gravel travel surface | | | | |
| | 2) Folsom Road - Upsize & enlarge existing | • | | | |
| | culvert. Rip Rap. Resurface 400' of gravel | \$8,500 | Medium Term | Road | Deferred – Lack of |
| | travel surface. Raise road profile. | | | Commissioner | funds |
| | 3) Raise elevation of floor in furnace | | O | Road | Deferred – Lack of |
| | room at fire station | \$30,000 | Short Term | Commissioner | funds |
| | 4) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Littleton | 1) Carson Road - Two culverts | *** | | | Deferred – Lack of |
| | | \$85,000 | Short Term | Public Works | funds |
| | 2) Wiley Road - One culvert | | | . | Deferred – Lack of |
| | | \$25,000 | Short Term | Public Works | funds |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|---------------|--|-------------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 3) Hillsiding Road - Nine culverts | | | | Deferred – Lack of |
| (Littleton) | | \$25,000 | Medium Term | Public Works | funds |
| | 4) Shanks Road - Three culverts | | | | Deferred – Lack of |
| | | \$8,000 | Medium Term | Public Works | funds |
| | 5) Gillen Road - One culvert | | | | Deferred – Lack of |
| | | \$14,000 | Short Term | Public Works | funds |
| | 6) Ingraham Road - One culvert | | | | Deferred – Lack of |
| | | \$5,000 | Short Term | Public Works | funds |
| | 7) Front Ridge Road - Six culverts | | | | Deferred – Lack of |
| | | \$30,000 | Medium Term | Public Works | funds |
| Madawaska | 1) Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| | 2) Acquisition/demolition – 1 property; | | | Contractor | Completed 2010 |
| | deed restricted to open space | \$192,477 | Completed | Public Works | HMPG |
| | 3) Grandmaisson Avenue – Catch basin, | | | | |
| | Drainage pipe | \$4,380 | Short Term | Public Works | Completed |
| | 4) Gendreau Road – Upsize culvert | \$96,000 | Short Term | Public Works | Completed |
| | 5) Golf Course Road – Upsize culvert | \$30,000 | Short Term | Public Works | Temporary fix 2018 |
| | 6) Pelletier Avenue – Upgrade culvert | \$10,000 | Short Term | Public Works | New Project |
| | 7) Third & Girard – Upgrade culvert | \$10,000 | Short Term | Public Works | New Project |
| | 8 Dufour Road Repair head of culvert to | \$7,500 | Short Term | Public Works | New Project |
| | redirect water | | | | |
| Mapleton | 1) NOMACCA Drive - Relocate access road | | | | |
| | away from Aroostook River approx. 600', fill | \$1,000,000 | Long Term | Public Works | Deferred – Lack of |
| | & rip rap | | | | funds |
| | 2) Teakettle Brook - Upsize culvert with | | | | Deferred – Lack of |
| | stream crossing culvert | \$150,000 | Medium Term | Public Works | funds |
| | 3) Create inventory of all town owned | | | | Deferred – Lack of |
| | roads and drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| Merrill | Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$15,000 | Long Term | Public Works | funds |
| | | | | | |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|---------------|---|-----------------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 1) Clark Road - 24" x 50' cmp to 36" x 50' | | | | Deferred – Lack of |
| Mars Hill | cmp & rip rap, elevate 250' of road bed | \$25,000 | Medium Term | Public Works | funds |
| | 2) Mountain Road - Upsize (2) 24' x 40' | | | | Deferred – Lack of |
| | cmps to 36" x 40' rip rap & ditch 300' | \$25,000 | Medium Term | Public Works | funds |
| | 3) East Ridge Road – Upgrade 3 culverts at | | | | Deferred – Lack of |
| | Gizoquit Brook | \$60,000 | Short Term | Public Works | funds |
| Monticello | 1) Jones Road – Reconstruct road | \$25,000 | Short Term | Public Works | New |
| | 2) Hoyt Road – Upgrade culverts and repair | | | | |
| | road | \$20,000 | Short Term | Public Works | New |
| | 3) Hillsiding Road - Upgrade culverts and | | | | |
| | repair road | \$15,000 | Short Term | Public Works | New |
| | 4 Bell Road – Install guard rails and repair | | | | |
| | roads | \$15,000 | Long Term | Public Works | New |
| | 5) Fullerton Road - Berm and seed, ditch | | | | Still repairing |
| | 700' of road rip rap & coffer dam | \$25,000 | Short Term | Public Works | sections |
| | 6) Install dry hydrants | | | | Deferred – Lack of |
| | | \$25,000 | Long Term | Public Works | funds |
| New Sweden | Generator(s) – Install generators as needed | _ | | | Deferred – Lack of |
| | at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Perham | High Meadow Road - Install underground | | | | Deferred – Lack of |
| | channels for drainage, elevation, ditching & | \$295,000 | LongTerm | Public Works | funds |
| | culverts | | | | |
| Portage Lake | 1) West Road - Install culverts 2 – 18" x 20' | | | | Completed |
| | HDPE cross culverts, gravel and pavement | \$4,160 | Short Term | Public Works | |
| | repair | | | | |
| | 2) West Road - Ditching 550' and 3 – 18" | A | | | Completed |
| | HDPE culverts, gravel and pavement repair | \$5,100 | Medium Term | Public Works | |
| | 3) West Road - Stabilize stream bank & | A | O | 5 | Completed |
| | culvert inlet/outlet w/geotextile and rip rap | \$1,900 | Short Term | Public Works | |
| | 4) Generator(s) – Install generators as | # 40.000 | 0, | • | |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | Completed |
| | | | | | |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|-----------------|--|-------------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 1) Burlock Road - Ditching and rip rap | \$14,000 | Medium Term | Public Works | Completed 2019 |
| Presque Isle | 2) Lombard Road - Culvert | | | | Deferred – Lack of |
| | | \$10,000 | ShortTerm | Public Works | funds |
| | 3) Henderson Road – Triple 36-inch | | | | Deferred – Lack of |
| | Culverts | \$42,000 | Short Term | Public Works | funds |
| | 4) Install dry hydrants | | | | Deferred – Lack of |
| | | \$30,000 | Long Term | Public Works | funds |
| | 5) Ginn Road - Culverts and rip rap | \$20,000 | Completed | Public Works | Completed 2004 |
| | | | | | and 2020 |
| | 6) Ashby Road - Ditching and rip rap | \$15,000 | Completed | Public Works | Completed 2003 |
| | 7) Main Street - Upsize culvert with box or | | | | |
| | arch culvert | \$35,000 | Completed | Public Works | Completed 2003 |
| | 8) Fort Road (Route 163/167 from North | | | | |
| | Street –Maple Grove Road - ditching | \$82,000 | Short Term | Public Works | Planned for 2021 |
| | 9) Easton Road (Route 10) east of Egypt | | | | |
| | Road – drainage improvements | \$199,000 | Short Term | Public Works | Planned for 2021 |
| | 10) US Route 1 (south) 0.27 mile N of | | | | |
| | Westfield Town Line – bridge culvert rehab | \$1,170,000 | Medium Term | Public Works | Planned for 2023 |
| Reed Plantation | Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| St. Agatha | 1) Airport Road - Create Ditching | \$15,000 | Completed | Public Works | Completed |
| | 2) Marquis Road - create better ditching & | | | | |
| | divert water to culvert | \$20,000 | Completed | Public Works | Completed |
| | 3) Marquis Road - Install culvert to access | | | | |
| | flow from the field | \$25,000 | Completed | Public Works | Completed |
| | 4) Brook Road - Create buffer zone | | | | Deferred – Lack of |
| | | \$50,000 | Long Term | Public Works | funds |
| | 5) Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$25,000 | Long Term | Public Works | funds |
| | 6) Flat Mountain - Buffering and ditch work | \$10,000 | Completed | Public Works | Completed |
| | 7) Plein Road - Buffering and ditching | \$12,000 | Completed | Public Works | Completed |
| | 8) Demolish treatment plant in floodplain | \$30,000 | Completed | Public Works | Completed |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|---------------|--|-----------|-------------|--------------|---------------------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | | | | | Deferred – Lack of |
| St. Francis | Sunset Drive - Culverts & ditching | \$20,000 | Medium Term | Public Works | funds |
| St. John | Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$20,000 | Long Term | Public Works | funds |
| Sherman | 1) Create inventory of all town owned | | | | Deferred – Lack of |
| | drainage (GPS) | \$20,000 | Long Term | Public Works | funds |
| | 2) Cold Brook and Gallison Roads – | | | | Deferred – Lack of |
| | ditching & culverts | TBD | Long Term | Public Works | funds |
| | 3) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds w |
| Unorganized | 1) Benedicta - Aroostook Road - | | | | Completed |
| Territory | Pavement reclaim/graded paving/striping | \$200,000 | Completed | Public Works | July/August 2017 |
| | 2) Connor/Sinclair/Madawaska Lake/E | | | | Completed Sept |
| | Plantation – pavement crack sealing 5 mi | \$40,000 | Completed | Public Works | 2018 |
| | 3) Connor – Madawaska & Haney Road – | | | | Completed Aug |
| | Ditching, paving approx. 1 mile | \$100,000 | Completed | Public Works | 2018 |
| | 4) Benedicta – Aroostook Road – Annual | | | | On-going (annual |
| | ditching (5-6 days) | \$25,000 | Short Term | Public Works | maintenance) |
| | 5) Connor & Sinclair – Haney, West Gate | | | | |
| | & Shore Roads – Pavement, post- | | | | Completed |
| | pavement shoulder build-up approx. 2.5 mi | \$225,000 | Completed | Public Works | Sept 2019 |
| | 6) Madawaska Lake – Lake Shore Drive – | | | | Completed |
| | Shoreline rip-rap approx. 400 feet | \$25,000 | Completed | Public Works | Nov 2020 |
| | 7) Cary Township- Wilcox & Smith Roads | | | | On-going – 2 nd year |
| | Excavate shoulder materials, ditching, | | | | of 5-year de- |
| | cross culvert upgrades | \$40,000 | Long Germ | Public Works | organization plan |
| | 8) Oxbow North Township – Oxbow Road | | | | On-going – 4 th year |
| | Ditching, culvert upgrades, road surface | \$100,000 | Long Term | Public Works | of 5-year de- |
| | rehabilitation on unpaved portion 9 miles | | | | organization plan |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|---------------|---|-----------|-------------|--------------|----------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| Van Buren | 1) St. Mary's Road - Two sections-1,000 ft., | | | | Deferred – Lack of |
| | raise, rip rap, enlarge culverts | \$45,000 | Long Term | Public Works | funds |
| | 2) Lake Road - Ditch, rip rap, raise road & | | | | Deferred – Lack of |
| | change culverts as needed for a distance of | \$78,000 | Long Term | Public Works | funds |
| | 2,000 feet | | | | |
| | 3) Alexander Road - Raise, grade, rip rap & | | | | Deferred – Lack of |
| | change culverts as needed for 3,000 feet | \$90,000 | Long Term | Public Works | funds |
| | 4) Acquisition/Demolition - 6 properties; | | | Contractor | Completed 2012; |
| | deed restricted to open space | \$371,405 | Completed | Public works | HMGP grant |
| | 5) Violette Brook - Rip Rap & Stabilize | TBD | Completed | Public Works | Completed in 2007 |
| | bank | | - | | • |
| | 6) DOT Project in conj. with Van Buren | | | | |
| | Public Works - Resolve under-sized | TBD | Long Term | Public Works | Deferred – Lack of |
| | culvert issues attempting to leverage federal | | | | funds |
| | highway funds | | | | |
| | 7) DOT Project in conf. with Van Buren | | | | |
| | Public Works - Resolve proper drain issues | \$97,500 | Long Term | Road | Deferred – Lack of |
| | relative to Champlain & Route 1 area | | | Commissioner | funds |
| | 8) Generator(s) – Install generators as | | | | Deferred – Lack of |
| | needed at critical facilities | \$10,000 | Short Term | Contractor | funds |
| Wade | 1) New Dunton Road - One bridge | \$11,000 | Long Term | Public Works | Completed |
| | 2) South Wade Road - Install 6 culverts and | | | | Several culverts |
| | guardrail | \$100,000 | Medium Term | Public Works | replaced need |
| | | | | | guard rails on river |
| | | | | | side of road |
| | 3) Gardner Creek – add drainage tile under | | | | Deferred – Lack of |
| | road and build up | \$10,000 | Medium Term | Public Works | funds |
| | 4) North Wade Road – Add guard rails | | | | |
| | along edge of brook | \$50,000 | Long Term | Public Works | New |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Town | | Estimated | Time | Responsible | |
|---------------|--|-------------|-------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| Wallagrass | 1) Rip rap to protect bridge | | | | Deferred – Lack of |
| | | \$11,830 | Long Term | Public Works | funds |
| | 2) Soldier Pond Road - Acquisition of six | | | | Deferred – Lack of |
| | homes | \$350,000 | Long Term | Public Works | funds |
| | 3) Church Street - 500 feet road elevation | | | | Deferred – Lack of |
| | | \$22,500 | Medium Term | Public Works | funds |
| Washburn | 1) Porter, Woodman, Wilder, and Berce | | | | Completed. Berce |
| | Streets – Study costs and feasibility to | \$4,000,000 | Long Term | Public Works | & Woodman done |
| | dredge, ditch, upgrade culvert and install | | | | several years ago, |
| | catch basins, underground drain to brook | | | | Porter & Wilder |
| | | | | | done 2020 |
| | 2) Emergency communication equipment | | | | |
| | - install 3 backup generator system | \$20,000 | Long Term | Public Works | New Project |
| | 3) Mill Pond - Remove culverts, upgrade | | | | Completed. Dam |
| | with bridge to eliminate flooding | \$250,000 | Long Term | Public Works | removed with DEP |
| | | | | | grant; culverts |
| | | | | | removed. No new |
| | | | | | bridge |
| | 4) Gardner Creek Road - Upsize culverts & | | _ | | Deferred – Lack of |
| | upgrade with bridge | \$1,000,000 | Long Term | Public Works | funds |
| | 5) Caribou Lake Road - Control & remove | | _ | | |
| | beavers and upgrade culvert | \$4,000 | Completed | Public Works | Completed |
| | 6) Annis Road – Road build up with bridge | \$500,000 | Long Term | Public Works | New Project |
| Westfield | 1) Tweedie Road - Two culverts | \$60,000 | Medium Term | Public Works | Completed |
| | 2) Miller Road - Three culverts | | | | Deferred – Lack of |
| | | \$40,000 | Medium Term | Public Works | funds |
| | 3) Shorey Road - Three culverts | \$10,000 | Short Term | Public Works | Completed |
| | 4) Cambridge Road - One culvert | \$2,500 | Short Term | Public Works | Completed |
| | 5) Simpson Road - One culvert | \$4,000 | Short Term | Public Works | Completed |
| | 6) Young Lake Road - Three culverts | \$6,000 | Short Term | Public Works | Completed |
| | 7) Viner Road - One Culvert | \$2,500 | Short Term | Public Works | Completed |
| | | | | | |
| | | | | | |

| Project (in Priority Order) stmanland Road – Ditch and upsize ts le Madawaska Lake Road - Raise at bridge for 500 feet, install culverts rris Hill Road - Four culverts D Cropley Road – Upsize culvert opley Road south side, east of 180 ey Road - Ditching st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$15,000 \$33,000 \$7,000 \$2,000 \$2,500 \$2,000 \$2,000 | Long Term Long Term Completed Short Term Short Term Short Term | Public Works Public Works Public Works Public Works Public Works | New Project Deferred – Lack of funds Completed Completed or |
|---|---|---|---|--|
| cle Madawaska Lake Road - Raise at bridge for 500 feet, install culverts ris Hill Road - Four culverts O Cropley Road - Upsize culvert opley Road south side, east of 180 ey Road - Ditching st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$33,000 \$7,000 \$2,000 \$2,500 \$2,500 | Long Term Completed Short Term Short Term Short Term | Public Works Public Works Public Works Public Works | Deferred – Lack of funds Completed |
| cle Madawaska Lake Road - Raise at bridge for 500 feet, install culverts ris Hill Road - Four culverts O Cropley Road - Upsize culvert opley Road south side, east of 180 ey Road - Ditching st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$33,000 \$7,000 \$2,000 \$2,500 \$2,500 | Long Term Completed Short Term Short Term Short Term | Public Works Public Works Public Works Public Works | Deferred – Lack of funds Completed |
| at bridge for 500 feet, install culverts rris Hill Road - Four culverts O Cropley Road – Upsize culvert opley Road south side, east of 180 ey Road - Ditching st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$7,000 \$2,000 \$2,500 \$2,500 | Completed Short Term Short Term Short Term | Public Works Public Works Public Works | funds Completed Completed or |
| rris Hill Road - Four culverts O Cropley Road - Upsize culvert Opley Road south side, east of 180 Ey Road - Ditching St of 7 Cropley Road - Culvert Orth of 106 Springer Road - Culvert | \$7,000 \$2,000 \$2,500 \$2,500 | Completed Short Term Short Term Short Term | Public Works Public Works Public Works | Completed or |
| O Cropley Road – Upsize culvert Opley Road south side, east of 180 Ey Road - Ditching St of 7 Cropley Road - Culvert of 106 Springer Road - Culvert | \$2,000 \$2,500 \$2,000 | Short Term Short Term Short Term | Public Works Public Works | Completed or |
| ppley Road south side, east of 180 ey Road - Ditching st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$2,500 \$2,000 | Short Term Short Term | Public Works | |
| ey Road - Ditching st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$2,000 | Short Term | | |
| st of 7 Cropley Road - Culvert rth of 106 Springer Road - Culvert | \$2,000 | Short Term | | 1 1 2 |
| rth of 106 Springer Road - Culvert | | ļ | Dublic Marks | deemed not |
| rth of 106 Springer Road - Culvert | \$2,000 | | Public Works | necessary |
| rris Hill Road – shoulder grading and | | Short Term | Public Works | Deferred – Lack of funds |
| maintenance | \$7,500 | Short term | Public Works | New Project |
| ving - Springer, Butterfield, and Dark roads | \$245,000 | Short Term | Public Works | New Project |
| ris Hill Road – Reconstruct road base urface on eastern half of road | \$400,000 | Medium Term | Public Works | New Project |
| ss Brook - Culverts and guardrails | \$25,000 | Medium Term | Public Works | Deferred – Lack of funds |
| d River Road - Culverts and rails | \$75,000 | Long Term | Public Works | Deferred – Lack of funds |
| ng along both sides of roadway | \$20,000 | Long Term | Public Works | Deferred – Lack of funds |
| tion Road – Culvert | \$10,000 | Short Term | Public Works | Deferred – Lack of funds |
| | | | | |
| 1(| | g along both sides of roadway \$20,000 ion Road – Culvert | g along both sides of roadway \$20,000 Long Term ion Road – Culvert | g along both sides of roadway \$20,000 Long Term Public Works ion Road – Culvert |

| Town | | Estimated | Time | Responsible | |
|---------------|--|-----------|------------|--------------|--------------------|
| Aroostook Co. | Project (in Priority Order) | Cost | Frame | Agency | Status |
| | 1) McIntyre Road - Elevate road & install 1, | | | | Deferred – Lack of |
| Woodland | 36" culvert | \$15,000 | Long Term | Public Works | funds |
| | 2) Sealander Road - Upsize culvert, rip rap | | | | Completed 2005; |
| | & install guard rail | \$23,675 | Completed | Public Works | DR-1371 HMGP |
| | | | | | grant |
| | 3) Skidgel Road - Elevate road | | | | Deferred – Lack of |
| | | \$15,000 | Long Term | Public Works | funds |
| | 4) Pratt Road - Elevate road | | | | Deferred – Lack of |
| | | \$25,000 | Long Term | Public Works | funds |
| | 5) Langley Road - Upsize culvert, add rip | | | | Completed 2005; |
| | rap | \$25,860 | Completed | Public Works | DR-1371 HMGP |
| | | | | | grant |
| | 6) Davis Road - Elevate road | | | | Deferred – Lack of |
| | | \$25,000 | Long Term | Public Works | funds |
| | 7) Everett Road - Elevate road and install | | | | Deferred – Lack of |
| | one culvert | \$20,000 | Long Term | Public Works | funds |
| | 8) Thibodeau Road - Ditching along both | | | | Deferred – Lack of |
| | sides of road | \$15,000 | Short Term | Public Works | funds |
| | 9) Brown Road - Ditching | \$20,000 | Completed | Public Works | Completed |